

Abstract Notification dated 13th April 1933.

The attention of the public is invited to the notification published in pages 435 and 437, Part VI of the *Mysore Gazette*, dated 20th April 1933 calling for tenders for the work of restoring Mallandahalli Doddakere, Registered No. 151—877 of Kolar Taluk.

The last date of receipt of tender in the office is upto 2 P.M. on 2nd May 1933.

C. T. NARASIMHA IYENGAR,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 17th April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. of 22nd May 1933 for constructing Administrative Block of McGann Hospital at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. to 5 P.M. on working days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates both in words and figures at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 3,000 (three thousand) in cash or Government Promissory notes, as earnest money and be superscribed "Tender for Constructing McGann Hospital at Shimoga" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary to Government, P.W.D. who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. Secretary to Government, P. W. D., also reserves the right to accept or reject any portion of tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after the acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes of any kind, the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Machinery or tools, etc., will be supplied, if available, in the Divisional stores and rent recovered at 25 per cent for plant and machinery and 24 per cent for tools exclusive of maintenance and repair charges during work which should be borne by the contractor.

13. Lumpsum provisions are subject to modifications as data worked out during execution for individual items of work under lumpsum provisions, the rates tendered for similar items of work will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

14. No representations regarding rates, etc., from the rejected tenderers will be considered.

15. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by contractor.

16. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity will summarily be rejected.

17. Specifications for works are those recognised by the Mysore Public Works Department and Marryat's specifications.

18. The contractor shall hold himself responsible for the good behaviour of his employees of all grades.

Abstract estimate for constructing Superstructure of the Administrative Block of
McGann Hospital at Shimoga.

No.	Items of work	Unit	Quantity
1	Boring holes in sill slabs 5" x 3½" x 4" for fixing door frames ..	Each	50
2	Burnt brick in lime mortar ..	C.ft.	23,123
3	Wirecut brick in cement mortar (wirecut brick supplied departmentally).	"	135
4	Burnt stone slab 6" thick dressed and fixed in mortar for lintels.	Sft.	1,593
5	Raw stone templates of trusses 9" thick fixed in mortar with two line dressing including boring four holes for holding down bolts.	"	318
6	Chunnam plastering finished smooth.	Sqr.	379
7	White washing, two coats ..	"	506
8	Marble flooring with 18" x 18" x 1" thick slabs fixed in chunnam mortar diagonally with border on 3" thick stone jelly concrete including pointing in white cement polishing for operation theatre.	Sqr. ft.	20'06
9	9" shell lime skirting for above ..	R.ft.	78
10	Milk white glazed tile dado fixed in cement with superior 6" x 6" tiles including angles with 3" green borders and 2" cornice, etc., including pointing with plaster of paris, etc., complete.	Sqr.	18'02
11	6" partition walls in brick in mortar with Xmet reinforcement for every alternative course including chunnam plastering on both the sides.	"	17'14
12	Red Marseilles tiles 8" x 8" flooring in chunnam mortar including cement pointing.	"	4,954
13	Colour washing to basement ..	"	31'71
14	Plain parapet wall in brick in mortar 2 feet high and 9" thick including plastering top and bottom mouldings and pillaster, etc., complete as per design.	R.ft.	674
15	12" cornice at terrace level as per design ..	"	678
16	Teak wood pendants at eaves ..	Each	16
17	Do finials at hips ..	"	6
18	Do plain eave board 9" x 1" as per design ..	R.ft.	568
19	1½" thick cudduppah slab wall plates fixed in mortar for terrace.	Sqr.	15'22
20	Bhadravathi cast iron pillars 9" diameter with capital and base 9 feet high including bolts as per design.	Each	62
21	Brick circular half columns 9" dia. finished as above ..	"	16
22	Jack arch terrace one course in edge and one in flat with 4½" angle brick jelly concrete laid in unslaked lime with proper slope with 3 courses of flat tiles first course dipped in cement including plastering on both sides, etc., complete.	Sqr.	52'00
23	Wrought iron trusses for 20 feet and 25 feet spans as per detailed drawings including cleats bed plates holding down bolts, etc., and hoisting and fixing in position with one coat of anticorrosive paint.	Cwt.	153
24	Roofing with 1st class Mangalore tiles on 2" x 1" teak reepers including ceiling tiles and fixing eave tiles with wires (separate rates for each kind of tiles to be quoted).	Sqr.	98'37
25	Teak wood wrought and put up including two coats of wood oiling.	C.ft.	481'00
26	Mangalore pattern ridge tiles set in mortar including cement pointing.	R.ft.	458
27	Cement concrete U shaped drain 9" x 9" all round plinth thickness of concrete 3"	"	1,193
28	4" x 3" C. I. rain water down pipes with necessary levels of sets, shoes head, etc., complete including fixing with iron clamps.	"	896
29	Iron clamps, etc., wherever necessary for fixing girders, etc. ...	Lumpsum	

No.	Items of work	Unit	Quantity
30	Teakwood doors with 4" x 6" frames with 1½" thick shutters 4½ feet panelled and top 4 feet glazed with ground glass and 1½" Bhadravati C. I. fret work as per approved design, with 6 brass parliamentary hinges 2 of 18" brass barrel bolts 2 of 9" brass bolts one 6" bolt 2 pairs brass down knobs with brass rim lock and China hinges, etc.	S.ft.	710
31	Do do do do 5" x 4" down frames without C. I. fret work with specification and fittings same as above.	"	340
32	Do do do do with 1" thick double panelled shutters as above	"	242
33	Do do do do with double springed hinges with above specification.	"	267
34	Teakwood windows with 5" x 3½" frame 1½" thick panelled shutters in four halves fixed out side with brass parliamentary hinges and 1½" thick glazed shutters in four halves fixed inside with ground glass and brass fittings, etc., complete.	"	1,176
35	Critical windows 4' x 7½' for operation theatre (windows supplied departmentally).	Each	3
36	Teakwood ventilators with ground glazed shutters for bath rooms.	S.ft	64
37	C. I. Rectangular ventilator as per approved design	"	520
38	Rolled steel joists Tatas or British standard, including hoisting and fixing with one coat of paint.	Cwt.	293.25
39	Shell line plastering to operation theatre complete	Sqr.	8.63
40	Boxing lintels with brick in mortar and plastered complete	R.ft.	435
41	Painting with grey graphits paint	Sqr.	86.92
42	Flooring with 1½" thick cudduppah slabs on 3" stons jelly concrete bed including cement pointing, etc., complete	"	35.18

G. SESHAGIRI RAO,
Executive Engineer.

KADUR DIVISION.

Abstract Notification.

The attention of the public is invited to the Notice calling for tenders for layout of Sanigere-Huligere road, published on page 405 of part VI of *Mysore Gazette* of 13th April 1933.

The last date for receiving tenders is 1st May 1933. Earnest money to be furnished is Rs. 110.

Notification.

It is hereby notified for the information of the general public that the right of fishery of Ayyanakere Tank, Kadur Taluk, will be sold by public auction on Friday the 28th April 1933, by the Assistant Engineer, Kadur Sub-Division. Intending bidders may appear and purchase the same in the auction.

L. A. H. WINCKLER,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT CENTRAL DISTILLERY, BANGALORE.

Notification No. 41. 336—32-33, dated 15th April 1933.

Tenders are hereby invited for the exclusive privilege of transporting underbond country spirits in motor lorries from the Government Central Distillery, Bangalore, to the Bangalore City Railway Goods Shed and to the arrack bonded depots as noted below for a period of one year from 1st July 1933 to 30th of June 1934.

- | | |
|---|---------------------------------|
| 1. Railway Goods Shed, Bangalore City. | 4. Arrack Bonded Depot, Hoskote |
| 2. Arrack Bonded Depot, Bangalore City. | 5. Do Devanhalli |
| 3. Arrack Bonded Depot, Anekal | 6. Do Nelamangala |
| | 7. Do Magadi |
| | 8. Do Kankanhalli |